EDS
Environmental Data Services


PLATFORM BROCHURE
BUILT IN AUSTRALIA

EDS FLOWSENSE

The whole network. Understood.

Live operations, infiltration and inflow, pump stations and calibrated hydraulic models, on one validated record. One platform, where there used to be four suppliers.

MONITOR · ANALYSE · ENGINEER · DELIVER



Four suppliers. Or one platform.

Doing this properly has meant a logger portal, a spreadsheet study, a modelling engagement and a fortnight of reporting. Each has its own format, and somebody retypes the numbers between them. FlowSense puts the whole chain on one record.

01	02	03	04	05	06
Sense	**Record**	**Operate**	**Analyse**	**Engineer**	**Decide**
The reading in the chamber, from any logger or SCADA	Validated, timed by the logger, never half loaded	Alarms, fleet health, blockages, pump stations	Infiltration and inflow in kilolitres, storm by storm	Calibrated models, the heat map, the capital plan	Board reports and feeds, under your own name

USUALLY BOUGHT AS

A logger portal Live readings and alarms for one brand of instrument	**A study** A spreadsheet, once a year	**A consultancy** A model, delivered as a PDF	**A fortnight** Copying charts into a document

WITH FLOWSENSE

EDS FlowSense One record. One subscription. Every stage, and nothing retyped between them.

No other platform sold in Australia carries a reading the whole way, from the chamber to the capital plan, on one record and in one subscription.

The same number, everywhere

The figure in the board paper and the reading in the chamber are one number. You can trace one to the other.

Answers in the meeting

You can check Monday's overflow against the rain, the sites upstream and the calibrated model in minutes, not in a scope of works.

Evidence that stays yours

When the programme is funded, the working is still there. You can re-run it and export it in open formats.

60s between refreshes of the whole network

5 ways in from your SCADA, no EDS software on it


8 blockage signatures, six of them from level alone

90 days free trial, on your own flow history

NETWORK OVERVIEW

Every site, every minute. Worst first.

The Overview opens with the sites that need attention, listed beside a map that shows where they are. It refreshes every sixty seconds, on any screen.



1 Six figures across the top

Five open their own list. Alarms to acknowledge are kept apart from any still breaching.

2 Since you last looked

One line on what changed since your last visit: alarms raised, blockage warnings, sites gone quiet.

3 Needs attention, worst first

One row per site with its reason: alarms newest first, then recent failures, then the backlog.


4 Where it is


The map beside the list circles the site whose row you point at. Rain radar is one click away.

THE SITE WORKSPACE

Whatever the site measures.

Flow and depth, pump states, pH, conductivity, rain or gas all land on one record. Each is drawn the way that suits what it measures, with the flow's normal range behind it.





Against its own usual

A chip by the name says how far the site sits from its own pattern for the hour.

Rain where it fell

Hourly rain from the site's gauge or its own model cell, shown above the flow in the hour it fell.


Two sites, one chart

Lay another site over this one, shifted in time when the flow takes hours to arrive.

FLEET HEALTH AND ALARMS

The failing logger, named before it goes quiet.

A monitoring programme fails quietly. A battery flattens, a modem stops answering, and the quarter's report is already wrong. FlowSense watches the fleet itself.



A replace-by date for every battery

Projected from the site's own discharge trend and battery chemistry. A dying logger becomes a planned visit.

Late, judged site by site

Offline means a site missed its own delivery deadline, so a twice daily logger is never reported late at hour three.

Alarms that reach a person

Threshold, no data and pump condition rules send email and SMS once, when the state changes. They go to people, not to addresses.


Monday, in the inbox

Each reader gets a summary of their own network, waiting at the start of the week.

BLOCKAGE WATCH · EVERY GRAVITY SEWER SITE

Blockages found in dry weather, weeks before they overflow.

A sewer drains almost empty overnight, and an obstruction shows in that trough long before anyone rings the council. Blockage Watch reads it twice a day and sets rain aside.



1 A decision, ranked

What needs a decision first, with its case number, then the sites behaving normally.

2 The call that saves a crew

The level is up because more water is arriving: increased load, not an obstruction. No jetting.

3 The numbers behind it

Overnight level and its trend, the headroom left in the pipe, evidence strength and dry days judged.

4 The case, to its close

A case opens at watch, goes to a crew by link, and closes itself once the site stays clear.


> Eight signatures, dry days only, and a one click backtest against your own overflow register. The hit rate you see is yours.

INFILTRATION AND INFLOW

Infiltration and inflow, in kilolitres.

"This catchment is wet" is not a business case. A volume, a peak, a lag and a percentage over dry weather flow is. FlowSense separates the storm from the sewage beneath it.

Peak RDII	RDII volume	Over dry weather flow	Storm lag	Dry weather flow, average	Night baseline
236.7 L/s	11,708 kL	26.12 %	1.8 h	17.30 L/s	6.77 L/s



Sanitary flow
The daily pattern, by day type

+

Groundwater infiltration
Tracked through the year

+

Rainfall derived inflow
Storm by storm

=

The metered total
Exactly. Nothing left over to argue about.

A baseline that moves

Dry weather flow from qualifying dry days only, so a weekend or a wet winter is never charged to the storm.

Catchment closure

Upstream against downstream, aligned on travel time, so you know how much of the flow is accounted for.

Ranked across the network

Which catchment first, which can wait, and which is not a rainfall problem at all.


A price on the water

Volumes priced at your own treatment and pumping rates, carried into the capital plan unchanged.

PSM · PUMP STATION MANAGER

Station flow from the pumps you already run. No flow meter.

A wet well fills as sewage arrives and empties as the pumps move it. So its level, the pump run states and its size make a flow record. EDS has built PSM on that since 1991.



1 **The station's figures first**

What arrived, what was pumped out, and the balance of the two over whole pump cycles.

2 **The wet well, in kilolitres**

An engineer's section of the well, with its start and stop levels and the volume each cycle moves.

3 **A briefing, in words**

What is worth watching and what is for the record, each with a button to its evidence.


4 **Pump condition, with a date**

Each pump against its rating, a warning when its output slips, and remaining useful life as a range.

I/I HEAT MAP

Severity painted onto the real network.

FlowSense attributes infiltration and inflow along the gravity network, by catchment and flow direction, and gives each estimate its confidence. The result is a ranked list of the pipes worth sending a camera down.



Six methods

You choose the method, and the platform says where your data cannot support it.

Along the pipes

Severity follows the way the sewer drains, not a circle drawn round a meter.

Confidence, 0 to 1

Pipes far from a gauge fade, rather than pretend to a number.

Your GIS, as supplied

The council's sewer layer loads from the file it came in, and the map exports as an A4 report.

01
Measure
Storm response quantified at each gauge

02
Attribute
Carried along the network by catchment and flow


03
Rank
Pipes ordered by how likely they are sources

04
Cost
The programme priced per kilolitre removed

MODELLING PROJECTS

A calibrated model you keep, not a report you file.

FlowSense runs calibration, validation and a dynamic wave network model as a project your engineers keep. When the question comes back next year, you run it again instead of commissioning it again.



EVERY STORM SCORED ON ITS OWN, TO THE CIWEM CODE OF PRACTICE

−15% to +25%	**−10% to +20%**	**1 hour**	**3 storms**
Simulated peak flow against observed	Event volume against observed	Peak timing, reported for review but never a failure on its own	The fewest a run needs to be called verified, with three in four passing

Dynamic wave hydraulics

Pipes, pumps, gates and control rules, run from the network's own dry weather state and exported to EPA SWMM 5.

The capital plan

Options ranked by net present value, benefit cost ratio and cost per kilolitre removed.

Your asset register, tested

The council's GIS checked against itself and the measured flow, each finding with its evidence.

REPORTS AND FEEDS

The board paper, from the record your operators use.

Each template is written for a different reader and generated from the same validated record, under your logo. The quarterly pack stops being a fortnight of copying charts.

A template for every reader

Executive summary, flow totals, flow analysis, engineering diagnostic, site investigation, network performance, and pump stations.

Context, not just totals

Each period is set against five other windows, including the same weeks last year.

Your document, not ours

Your logo and title throughout, as a branded PDF with contents and bookmarks, or a CSV bundle.

In the inbox, by the calendar


Daily, weekly or monthly by email, each over whole days, so one issue compares with the last.

Feeds on a schedule

CSV by SFTP or FTPS, CSV or JSON by MQTT, with run history. A failed send never skips a window.

A read API and webhooks


Your historian, BI stack or GIS reads the same record the reports are written from.



OFFICE AND FIELD

The office and the manhole see the same thing.

Your account works on a phone, with nothing to install and no second licence. What the crew finds sits beside the data it explains, where next year's engineer will find it.



Notes with photographs

Observation, maintenance and calibration notes, with photos and video from the phone in the crew's pocket.

Surveys that write the paperwork

The pre-installation survey fills in the inspection report, manhole diagram included.

A link for the contractor

A single use link with no login opens one job and nothing else. What they find comes back as a field note, photographs attached.

The instrument's history

Zero checks, reference readings and meter comparisons kept against the site, for the year somebody asks.

> No field app to licence, deploy or keep in step. The crew already carries the platform.

GETTING CONNECTED

Bring the fleet you own and the SCADA you run.

Nothing here asks you to replace an instrument or start your record again. Several logger brands, two SCADA systems and a decade of spreadsheets land in one account and read as one network.

IN

Your loggers
Collected by EDS, several manufacturers

Your SCADA sends
HTTPS push or MQTT, nothing installed on it

We read your system
API poll, on a schedule

We collect your files
From your SFTP or FTPS server

You drop files
Into an SFTP folder we host for you

Reviewed CSV import
Staged, checked, with a 30 day undo

One validated record

Field time kept
Never the time it was collected

Duplicates dropped
Anything can be safely re-sent

All or nothing
No half loaded day, ever

Unknown tags wait
A person maps them, not a guess

OUT

Back to your SCADA
Readings out, on a schedule

CSV and JSON feeds
CSV by SFTP or FTPS, CSV or JSON by MQTT

Read API and webhooks
For your historian or BI stack

Model exports
EPA SWMM 5, GeoJSON, Excel

Branded reports
PDF and CSV, under your name

Everything, on exit
Your record leaves with you

Rain at every site, without a separate subscription. FlowSense files hourly rainfall from the ECMWF forecast model for each site's own grid cell, in the hour it fell. It adds the odds of rain from the model's 51 member ensemble, and a running score of how right each outlook proved.

Commissioned with you. We set up every connection with your IT or SCADA people, using documents written for them. A connection is not done until a reading has arrived and been checked.

Hosted in Sydney
DigitalOcean's Sydney region

Encrypted in transit
Current TLS, with strict transport security

Two-factor sign-in
Time based codes, to RFC 6238

Access down to the channel
Roles, pages, sites and channels, set by you

A full audit trail
Who signed in, viewed, changed and exported

Tokens that only write
A leaked token cannot read a stored value

ONLY ON ONE RECORD

Eight things you will not find together anywhere else.

Each answers a question an authority is asked every year. Together, on one record and one subscription, they are the reason FlowSense exists.

01 **One record, end to end**
The reading in the chamber and the figure in the board paper are the same number, never retyped.

02 **Blockages read from the pipe**
Eight dry weather signatures that name the mechanism and the action, backtested on your own overflows.

03 **Flow from every pump station**
Station inflow and pump condition from the level and run signals you already have.

04 **Infiltration that adds up**
Sanitary, groundwater and rainfall derived flow, summing exactly to the metered total.

05 **Models you keep**
Storm by storm calibration, a dynamic wave network and a costed plan, in one workspace.

06 **Data both ways**
Your SCADA in five ways, and the validated record back out to it.

07 **Every number shows its working**
“How this is calculated” on the figures that matter, naming the method and the standard.

08 **A price on the page**
Per site, everything included, unlimited users, and no editions to choose between.

Built to the published standards, and tested against them

Each calculation cites the standard it follows, in the product, where your reviewer can read it.

CIWEM UDG Code of Practice, 2017 · WEF MOP FD-6 · WSA 02 Sewerage Code of Australia · AR&R 2019 and AS/NZS 3500.3 · QARTOD · EPA SWMM 5 · ISO 13381-1

> Built in Australia, for Australian networks: our sewerage codes, our rainfall guidance, and the clock your crews keep.

ONE SUBSCRIPTION

Every capability. Priced by the site.

Published, because a price you can only discover through a sales cycle is itself a cost. No editions and no per user fees. Everything in this brochure is in one subscription.

FIRST 20 SITES

$30

per site, per month

SITES 21 AND BEYOND

$20

per site, per month

WHAT THAT MEANS FOR A REAL NETWORK	SITES	PER YEAR	PER SITE, PER MONTH
Small shire	5	$1,800	$30
Regional council	20	$7,200	$30
Mid size council	50	$14,400	$24
Large regional network	90	$24,000	$22
Bulk utility	300	$74,400	$21

FREE TRIAL

$0

90 days of the whole platform, on your own uploaded flow history.

ASSISTED ONBOARDING

$2,500

Once: GIS, sites, alarms, SCADA and training. Waived from 50 sites.

GUIDED CALIBRATION

$7,500

Optional, per catchment, done with EDS. The tools are included.

The fine print, in full. AUD excluding GST, billed annually on twelve month terms. Bands are cumulative, so growth never re-prices the sites you have. A site is a monitored location with at least one active channel. Archived sites cost nothing. Unlimited users. SMS is the only pass-through charge, at carrier cost. These rates hold for the term and may change at renewal on 60 days written notice. Either side may end the subscription at renewal on 30 days notice, and your data exports with you in full.

SINCE 1991, EDS HAS MEASURED WATER AND WASTEWATER FOR


Logos are of organisations EDS has supplied, monitored or worked for since 1991; they are the trademarks of their owners and do not indicate use of FlowSense.

NEXT STEP

See it on your own network.

Send us the flow history you already hold. We will stand up a 90 day trial on it and show you your infiltration ranking the same afternoon.

Or book a live demonstration, and bring your hardest question about how a figure was calculated.



CALL

1300 721 683

Monday to Friday,
7:30 am to 4:30 pm

EMAIL

eds@e-d-s.com.au

ONLINE

www.e-d-s.com.au

THE PLATFORM

edsflowsense.au

HEAD OFFICE

Environmental Data Services
13/20-22 Ellerslie Road, Meadowbrook QLD 4131

FOUR OFFICES

Brisbane, Richmond NSW, Boronia VIC
and Adelaide SA

Every drop, measured.

EDS FlowSense brochure, EDS-FS-FLG-01, revision 1.3 of 12 October 2026, superseding revision 1.2 of 11 October 2026. Screens are photographed from the platform's demonstration account, whose sites and readings are synthetic. Capabilities are those of the released platform at the date of issue. Prices are the rates current at the date of issue. Logos are of organisations EDS has supplied, monitored or worked for since 1991; they are the trademarks of their owners and do not indicate use of FlowSense. Other third party names are the trademarks of their respective owners.

EDS Environmental Data Services

AUSTRALIAN OWNED AND OPERATED SINCE 1991